



When groundwater is encountered the lining joint shall not be made until pumping of groundwater has been discontinued for at least three days and no visible leakage is evident at the joint.

When welding the downstream side of a joint strip or flap, do not weld 6 to 8 inches at the pipe invert to provide relief of potential future groundwater buildup.

Ameron PROTECTIVE LINING DIVISION

T-LOCK® DETAIL FOR
GROUNDWATER RELIEF

DRAWN	JPG	11/07	PLD-TL-390	REV
APPV'D				0